



©2022 Landscape Structures. All Rights Reserved.








Cologne VFW Park Address City, State ZIP Nate Kells

PRELIMINARY BUDGET - THIS IS AN ESTIMATE & NOT A FORMAL QUOTE

FRELIVINARY BODGET - THIS IS AN ESTIMATE & NOT A FO		Possible		
	Preliminary Budget Possible Additions	Reductions	QTY	Notes
Play Equipment	7			
Design - VFW Park OPT 2	143,830.00			List Price of Equipment
State Contract Discount	(11,506.40)		8%	State Contract #119795
Sales Tax - if applicable				
Equipment Installation (Man Hours & Concrete for Footings)	23,753.94			Full professional installation by Landscape Structures Certified Installers
Delivery of Play equipment	1,200.00			estimated / final quote will be provided
Per Diem	0.00			estimated / final quote will be provided
Mobilization	500.00			
Dumpster(s) - 30 Yard	525.00	(525.00)	1	Disposal of packaging material *Possible deduction if owner provides dumpster
Site work				
Excavation, Hauling & Disposal (new container)	11,488.75	(11,488.75)		*Possible deduction if general contractor does site prep
Demo, Excavation, Hauling & Disposal (existing container)	0.00			
Special Equipment (Lull, Lift, Compactor, etc.)	0.00			
Border Options				
Concrete Border Straight (LF)	20,768.13	(20,768.13)	470	Standard 6" W x 12" D w/ rebar *Possible deduction if sidewalk contractor does curbing
Subgrade Preparation				
Compacted Aggregate Base (Recycled Concrete or Class 5) (Tons)	6,446.97		267	Class 5 aggregate or recycled concrete (w/fines), delivery and installation . 4" - 6" compacted depth. Required for PIP & Synthetic Turf
Designation (UE)	0.00		_	installations
Drain Tile (LF)	0.00	1	0	Perforated Corrugated Drain Tile with Sock
Surfacing Poured In Place (PIP) & Synthetic Turf				
Surfacing Poured in Place (PIP) & Synthetic Turi				Budget estimate assumes use of Aromatic Binder (7 year warranty) and 50/50 mix of standard colors & black. Premium Colors have an
PlayBound Poured In Place by Surface America (Sq. Ft.)	145,557.16		5,147	additional. *Number is budgeted - A formal quote is needed
				additional. *Number is budgeted - A formal quote is needed
Chain Link Construction Fence (8' x 8' Panels)	0.00		0	Temporary construction fence.
Security Gurard	0.00		· ·	Site security needed around the clock for up to 72hours after PIP is installed. *Damage not warrantied
Security durant	0.00			Site security needed around the clock for up to 72 hours after 711 is instanced.
Site Restoration (Sg.Ft.)	0.00		0	Top soil, seed and blanket
(-1)	2.23			A CONTRACTOR OF THE CONTRACTOR
Payment & Performance Bonds	0.00			
	Budget Total Total Additions	Total Reductions		Total w/ Additions & Reductions
	342,563.54 0.00	(32,781.87)		309,781.67





©2022 Landscape Structures. All Rights Reserved.





Cologne - VFW Park

1164983-02-01-02 • 05.26.2022





